### **APPLICATION SPECIFICATION**

#### **GNSS/WIFI COMBO CERAMIC ANTENNA**

#### 1.0 SCOPE

This specification describes the antenna application and recommended PCB layout for the Molex GNSS/WIFI Combo Ceramic Antenna. This antenna has two feeding pads. One feeding pad is used for GNSS band and the other feeding pad is used for WIFI (2.4GHz/5GHz) band. The information in this document is for reference and benchmark purposes only. The user is responsible for validating antenna RF performance based on users own PCB and matching circuits.

All measurements are done of the antenna mounted on the recommended PCB with VNA Agilent 5071C and OTA chamber.

Antenna illustrations in this document are generic representations. They are not intended to be an image of any antenna listed in the scope.

#### 2.0 PRODUCT DESCRIPTION

#### A. DEFINITIONS OF TERMS

The antenna design is based on carrier size 3.2mm × 1.6mm × 1.1mm (Length\*Width\* Height). There are two feeding pads, two grounding pads, one fixing pad and antenna radiator. See figure 1.

1. FEEDING PAD

SMT mounted to feeding pad on PCB. The signal from the transmission line must feed into the feeding pad on the PCB.

2. GROUNDING PAD

SMT mounted to grounding pad on PCB.

3. FIXING PAD

SMT mounted to dummy pads on PCB. Anchoring the antenna to the PCB

4. ANTENNA RADIATOR

To act as a transducer that converts unguided electromagnetic wave to guided electromagnetic wave and vice versa.




FIGURE 1. GNSS/WIFI COMBO CERAMIC ANTENNA

REVISION:	ECR/ECN INFORMATION:	ΠΤLE:			SHEET No.	
Α	EC No: <b>121094</b>	GNSS/WI	<b>GNSS/WIFI Combo Ceramic Antenna</b>			
	DATE: <b>2017/08/25</b>				<b>1</b> of <b>23</b>	
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	<u>APPRO\</u>	/ED BY:	
2030070001		Hai Liu 2017/08/25 Benson Liu 2017/08/25 Chris Zhon			2017/08/25	

### **APPLICATION SPECIFICATION**

#### **B. REFERENCE IMPLEMENTATION**

#### I. REFERENCE PCB DESCRIPTION

The size of reference PCB design is 80mm\* 40mm \*0.8mm, which is used for this antenna performance verification. There are two feeding pads, two grounding pads and one fixing pad. The clearance size is also 6mm\*8mm.See figure 2.

#### 1. FEEDING PAD

The signal from transmission line must be fed into the feeding pad.

#### 2. GROUNDING PAD

The antenna must be SMT mounted to grounding pad on PCB.

#### 3. MATCHING CIRCUIT

It is necessary to reserve PCB space for "L" type matching circuits in this design. In order to adjust the return loss due to loading by the device housing and surroundings, the matching circuits need to be changed accordingly.

#### II. REFERENCE PCB LAYOUT




FIGURE 2: REFERENCE PCB LAYOUT


(Note: PCB Ground Size of 80 mm x 40 mm x 0.8 mm)

2030070001		Hai Liu 2017/08/25			2017/08/25		
DOCUMENT NUMBER:		CREATED / REVISED BY: CHECKED BY: APPRO		APPROV	ED BY:		
Α	DATE: 2017/08/25						
٨	EC No: <b>121094</b>	GNSS/WII	<b>GNSS/WIFI Combo Ceramic Antenna</b>				
REVISION:	ECR/ECN INFORMATION:	TITLE:	SHEET No.				

## **APPLICATION SPECIFICATION**

### III. ANTENNA PERFORMANCE AT RECOMMENDED LOCATION

The recommended antenna location is at the upper center of the PCB as shown in Figure 2.1.




### FIGURE 2.1 RECOMMENDED ANTENNA LOCATION

DESCRIPTION	Test Condition	Requirement				
Frequency Range	Measure antenna on recommended PCB through VNA E5071C	1561MHz	1575MHz	1602MHz	2.4-2.5GHz	5.15-5.85GHz
Return Loss	Measure antenna on recommended PCB through VNA E5071C	< -6 dB	< -10 dB	< -6 dB	< -6 dB	< -5.5 dB
Peak Gain (Max)	Measure antenna on recommended PCB through OTA chamber	0.9dBi	1dBi	0.3dBi	0.6dBi	1dBi
Avg. Total Efficiency	Measure antenna on recommended PCB through OTA chamber	>55%	>55%	>50%	>55%	>50%
Polarization	Measure antenna on recommended PCB through OTA chamber	Linear				
Input Impedance	Measure antenna on recommended PCB through VNA E5071C	50Ohms				

A	EC No: 121094  DATE: 2017/08/25		GNSS/WIFI Combo Ceramic Antenna			
2030070001		CREATED / REVISED BY: CHECKED BY: APPRO Hai Liu 2017/08/25 Benson Liu 2017/08/25 Chris Zhon		Chris Zhong	<del></del>	

### **APPLICATION SPECIFICATION**

#### 2.1RF PERFORMANCE AT REFERENCE LOCATION IN FREE SPACE







FIGURE 2.2 RETURN LOSS OF ANTENNA AT GNSS AND 2.4GHZ/5GHZ ON REFERENCE PCB AT REFERENCE LOCATION IN FREE SPACE







FIGURE 2.3 EFFICIENCY OF ANTENNA AT GNSS AND 2.4GHZ/5GHZ ON REFERENCE PCB AT REFERENCE LOCATION IN FREE SPACE

REVISION:	ECR/ECN INFORMATION: EC No: 121094  DATE: 2017/08/25	GNSS/WII	4 of 23			
DOCUMENT		CREATED / REVISED BY:	CREATED / REVISED BY: CHECKED BY: APPROV			
2030070001		Hai Liu 2017/08/25   Benson Liu 2017/08/25   Chris Zhor		Chris Zhong	2017/08/25	






FIGURE 2.4 PEAK GAIN OF ANTENNA AT GNSS AND 2.4GHZ/5GHZ ON REFERENCE PCB AT REFERENCE LOCATION IN FREE SPACE

2030070001		Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong	2017/08/25			
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	<u>APPRO</u> V	<u>ED BY:</u>			
A	DATE: <b>2017/08/25</b>							
٨	EC No: <b>121094</b>	GNSS/WII	<b>GNSS/WIFI Combo Ceramic Antenna</b>					
REVISION:	ECR/ECN INFORMATION:	TITLE:	<u>ITLE:</u>					

### APPLICATION SPECIFICATION

#### 3.0 REFERENCE DOCUMENTS

Sales Drawing: SD-2030070001

Product Specification: PS-2030070001

Packaging Information – Refer to the Molex related packaging drawings.

#### 4.0 RF PERFORMANCE AS A FUNCTION OF IMPLEMENTATION

#### 4.1 ANTENNA RF PERFORMANCE INFLUENCED BY NEARBY SHIELDING CAN

A shielding can with size of 20mm\*10mm\*2mm was used for this study.

An evaluation was done with 3 different distances from the antenna which located at the recommended location to the shielding can. The 3 distances are as following: 1mm, 3mm and 5mm.

From the study, we recommend that a shielding can should be placed at least 5mm away from the antenna. When the distance is less than 5mm, the antenna performance will be significantly degraded. Refer to figure 4.1.1-4.1.3.





Figure 4.1 SHIELDING CAN FIXED ON REFERENCE PCB

REVISION:	ECR/ECN INFORMATION:	TITLE:	SHEET No.				
A	EC No: <b>121094</b>	GNSS/WII	<b>GNSS/WIFI Combo Ceramic Antenna</b>				
	DATE: <b>2017/08/25</b>						
DOCUMENT NUMBER: CREATED / REVISED BY: CHECKED BY:		<u>APPROV</u>	<u>ED BY:</u>				
2030070001		Hai Liu 2017/08/25 Benson Liu 2017/08/25 Chris Zhon			2017/08/25		

# $\widehat{\text{molex}}^{\circ}$







FIGURE 4.1.1 RETURN LOSS COMPARISON AT GNSS AND 2.4GHZ/5GHZ OF SHIELDING CAN DISTANCE FROM ANTENNA







FIGURE 4.1.2 EFFICIENCY COMPARISON AT GNSS AND 2.4GHZ/5GHZ OF SHIELDING CAN DISTANCE FROM ANTENNA

	T NUMBER:	CREATED / REVISED BY: Hai Liu 2017/08/25			/ED BY: 2017/08/25	
Α	DATE: <b>2017/08/25</b>		GNSS/WIFI Combo Ceramic Antenna			
	EC No: <b>121094</b>	GNSS/WII				
REVISION:	ECR/ECN INFORMATION:	TITLE:	SHEET No.			






FIGURE 4.1.3 PEAK GAIN COMPARISON AT GNSS AND 2.4GHZ/5GHZ OF SHIELDING CAN DISTANCE FROM ANTENNA

REVISION:	ECR/ECN INFORMATION: EC No: 121094  DATE: 2017/08/25		GNSS/WIFI Combo Ceramic Antenna			
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	<u>APPROV</u>	ED BY:	
2030070001		Hai Liu 2017/08/25   Benson Liu 2017/08/25   Chris Zhor		Chris Zhong	2017/08/25	

### **APPLICATION SPECIFICATION**

#### 4.2 RF PERFORMANCE AS AN EFFECT OF PCB GROUND SIZE

Three kinds of PCB ground size have been evaluated and these configurations are shown in figure 4.2. Figure 4.2.1-4.2.3 comparatively show the return loss, the efficiency, and the peak gain of this antenna with three kinds of PCB. 60mm\*40mm is the recommended minimum PCB ground size for this antenna. When the ground size is less than 60mm\*40mm, the performance will be significantly decreased.





FIGURE 4.2 DIFFERENT GROUND PCB SIZES

REVISION:	ECR/ECN INFORMATION:	TITLE:	SHEET No.		
٨	EC No: <b>121094</b>	GNSS/WI	FI Combo Ceramic Ant	enna	0 of 22
Α	DATE: 2017/08/25		<b>9</b> of <b>23</b>		
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	<u>APPRO\</u>	ED BY:
2030070001		Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong 2017/08/2	







FIGURE 4.2.1 RETURN LOSS COMPARISON GNSS AND 2.4GHZ/5GHZ OF AN ANTENNA MOUNTED ON DIFFERENT GROUND SIZE







FIGURE 4.2.2 EFFICIENCY COMPARISON AT GNSS AND 2.4GHZ/5GHZ OF AN ANTENNA MOUNTED ON DIFFERENT GROUND SIZE

REVISION:	ECR/ECN INFORMATION: EC No: 121094  DATE: 2017/08/25		GNSS/WIFI Combo Ceramic Antenna			
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	<u>APPROV</u>	'ED BY:	
2030070001		Hai Liu 2017/08/25   Benson Liu 2017/08/25   Chris Zhoi		Chris Zhong	2017/08/25	

## **APPLICATION SPECIFICATION**



DEVICION. FOR/ECN INFORMATION. TITLE.




FIGURE 4.2.3 PEAK GAIN COMPARISON AT GNSS AND 2.4GHZ/5GHZ OF AN ANTENNA MOUNTED ON DIFFERENT GROUND SIZE

A	EC No: 121094  DATE: 2017/08/25	GNSS/WII	11 of 23		
2030070001		CREATED / REVISED BY: CHECKED BY: APPR Hai Liu 2017/08/25 Benson Liu 2017/08/25 Chris Zho		Chris Zhong	

CLIEFT No

### **APPLICATION SPECIFICATION**

#### 4.3 ANTENNA RF PERFORMANCE AS A FUNCTION OF LOCATIONS ON REFERENCE PCB

Two locations have been evaluated RF performance and these locations are shown in figure 4.3. Figure 4.3.1, figure 4.3.2, and figure 4.3.3 comparatively present the return loss, efficiency, and peak Gain at two locations. The antenna performance at these two locations have been optimized with matching circuits.

The performance of location 1 is much better than location 2. So location 1 (upper center location) is the recommended location for this antenna.





FIGURE 4.3 TWO LOCATIONS ON REFERENCE PCB

A	EC No: 121094  DATE: 2017/08/25	GNSS/WIFI Combo Ceramic Antenna			<b>12</b> of <b>23</b>
DOCUMENT NUMBER: 2030070001		CREATED / REVISED BY: Hai Liu 2017/08/25	CHECKED BY: Benson Liu 2017/08/25	APPROV Chris Zhong	<del></del>







Figure 4.3.1 RETURN LOSS OF ANTENNA AT GNSS AND 2.4GHZ/5GHZ AT TWO DIFFERENT LOCATIONS






Figure 4.3.2 EFFICIENCY OF ANTENNA AT GNSS AND 2.4GHZ/5GHZ AT TWO DIFFERENT LOCATIONS

REVISION:	ECR/ECN INFORMATION: EC No: 121094  DATE: 2017/08/25	GNSS/WIFI Combo Ceramic Antenna		enna	13 of 23
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	<u>APPROV</u>	'ED BY:
2030070001		Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong	2017/08/25




Figure 4.3.3 PEAK GAIN OF ANTENNA AT GNSS AND 2.4GHZ/5GHZ AT TWO DIFFERENT LOCATIONS

A SN35/WII I Combo Ceramic Antenna 14	ハヘナンス
	<b>4</b> of <b>23</b>
REVISION: ECR/ECN INFORMATION: TITLE:  SHE  GNSS/WIFI Combo Ceramic Antenna	HEET No.

### APPLICATION SPECIFICATION

#### 5.0 MATCHING NETWORK

#### 5.1 MATCHING NETWORK DESRICPTION FOR GNSS BAND

The "L" type matching circuit is recommended to be applied for this antenna at the recommended position on reference PCB. The sequence of parallel element and series element depends on the resistance of antenna in smith chart shows in Figure 5.1. Figure 5.2 shows the matching network for this antenna at GNSS band at the recommended position on reference PCB. The matching network is a series 5.6nH for GNSS Band.




FIGURE 5.1 CONFIGURE 1 FOR GNSS Band





FIGURE 5.2 RECOMMEND MATCHING NETWORK FOR GNSS Band


REVISION:	ECR/ECN INFORMATION:	TITLE:			SHEET No.	
٨	EC No: <b>121094</b>	GNSS/WI	FI Combo Ceramic Ant	enna	<b>15</b> of <b>23</b>	
Α	DATE: 2017/08/25					
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	<u>APPRO</u> \	/ED BY:	
2030070001		Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong	2017/08/25	

### **APPLICATION SPECIFICATION**

The following figure 5.3 and figure 5.4 are the return loss and smith chart comparison without and with the matching network for the antenna at GNSS Band on reference PCB ground size and at reference location.



#### FIGURE 5.3 RETURN LOSS OF ANTENNA WITHOUT AND WITH MATCHING ON REFERENCE PCB GROUND SIZE AT REFERENCE LOCATION



### FIGURE 5.4 SMITH CHART OF ANTENNA WITHOUT AND WITH MATCHING ON REFERENCE PCB GROUND SIZE AT REFERENCE LOCATION

	REVISION:	ECR/ECN INFORMATION:	TITLE:			SHEET No.
Α	EC No: <b>121094</b>	GNSS/WI	<b>16</b> of <b>23</b>			
	^	DATE: <b>2017/08/25</b>				10 01 23
	DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	<u>APPRO\</u>	/ED BY:
2030070001		030070001	Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong	2017/08/25


### **APPLICATION SPECIFICATION**

#### 5.2 MATCHING NETWORK DESRICPTION FOR 2.4G/5G BAND

A matching circuit is needed if the resonance frequency needs adjustment due to loading by the device housing and surrounding components effect.


Two matching configurations as shown in Figure 5.5 and Figure 5.6 are recommended for signal 2.4GHz band and 5GHz band matching, respectively. The combination of these two configurations can be applied for both of the two bands matching at the same time, which can be seen in Figure 5.7. Take configuration 1 for example, the matching network is a series capacitor followed with a parallel inductor. The sequence of series capacitor and parallel inductor depends on the resistance of antenna in smith chart. Furthermore, in some case, only one series capacitor or a parallel inductor can achieve matching purpose. These tips can also be used for configure 2 and the combination topology are shown in Figure 5.7.

Figure 6.8 shows the matching network for this antenna at 2.4GHz/5GHz at the recommended position on reference PCB. The matching network is a series 5.6pF capacitor following with a parallel 1.1nH inductance, and following with a parallel 0.2pF capacitor.



#### FIGURE 5.5 CONFIG 1 FOR 2.4GHZ BAND

#### FIGURE 5.6 CONFIG 2 FOR 5GHZ BAND






FIGURE 5.7 MATCHING TOPOLOGY FOR BOTH 2.4GHZ AND 5GHZ BAND

# FIGURE 5.8 RECOMMEND MATCHING NETWORK FOR 2.4GHZ/5GHZ

RI	EVISION:	ECR/ECN INFORMATION:	TITLE:			SHEET No.
٨	EC No: <b>121094</b>	GNSS/WI	FI Combo Ceramic Ant	enna	<b>17</b> of <b>23</b>	
	Α	DATE: <b>2017/08/25</b>				17 01 23
DOCUMENT NUMBER:		ΓNUMBER:	CREATED / REVISED BY:	CHECKED BY:	<u>APPROV</u>	/ED BY:
2030070001		030070001	Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong	2017/08/25

### **APPLICATION SPECIFICATION**

The following figure 5.9 and figure 5.10 are the return loss and smith chart comparison without and with the matching network for the antenna at 2.4GHz/5GHz on reference PCB ground size and at reference location.




FIGURE 5.9 RETURN LOSS OF ANTENNA WITHOUT AND WITH MATCHING ON REFERENCE PCB **GROUND SIZE AT REFERENCE LOCATION** 




FIGURE 5.10 SMITH CHART OF ANTENNA WITHOUT AND WITH MATCHING ON REFERENCE PCB GROUND SIZE AT REFERENCE LOCATION

REVISION:	ECR/ECN INFORMATION:	TITLE:			SHEET No.
Α	EC No: <b>121094</b>	GNSS/WI	FI Combo Ceramic Ant	enna	<b>18</b> of <b>23</b>
A	DATE: <b>2017/08/25</b>				10 01 23
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	<u>APPRO\</u>	/ED BY:
2030070001		Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong	2017/08/25

## **APPLICATION SPECIFICATION**





FIGURE 6.1 RADIATION PATTERN OF ATNENNA AT 1575MHZ AT RECOMMENDED LOCATION



# FIGURE 6.2 RADIATION PATTERN OF ATNENNA AT 2.45GHZ AT RECOMMENDED LOCATION

REVISION:	ECR/ECN INFORMATION:	TITLE:			SHEET No.
۸	EC No: <b>121094</b>	GNSS/WII	FI Combo Ceramic Ant	enna	<b>19</b> of <b>23</b>
Α	DATE: <b>2017/08/25</b>				190123
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	<u>APPROV</u>	/ED BY:
2030070001		Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong	2017/08/25




FIGURE 6.3 RADIATION PATTERN OF ATNENNA AT 5.45GHZ AT RECOMMENDED LOCATIN

REVISION:	ECR/ECN INFORMATION:	TITLE:			SHEET No.
٨	EC No: <b>121094</b>	GNSS/WII	FI Combo Ceramic Ant	enna	<b>20</b> of <b>23</b>
Α	DATE: <b>2017/08/25</b>				20 01 23
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	<u>APPRO\</u>	/ED BY:
2030070001		Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong	2017/08/25

7.0 ASSEN	BLY INSTRUCTIONS
	A. RECOMMENDED SMT REFLOW PROFILE
	See Management Palates. To the Contract Contract, contract and for the Contract Cont
	FIGURE 7.1 RECOMMENDED SMT REFLOW PROFILE
	B. MECHANICAL INTERFACE
	I. GENERAL DESCRIPTION  The overall antenna size is 3.2mm X 1.6mm X 1.1mm
	3.2mm
	l'enn
	1.1 mm

FIGURE 7.2 OVERALL ANTENNA SIZE

REVISION:	ECR/ECN INFORMATION:	TITLE:			SHEET No.
٨	EC No: <b>121094</b>	GNSS/WII	FI Combo Ceramic Ant	enna	<b>21</b> of <b>23</b>
A	DATE: <b>2017/08/25</b>				210123
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	APPRO\	/ED BY:
2030070001		Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong	2017/08/25



## **APPLICATION SPECIFICATION**

# 

#### **FIGURE 7.3 ANTENNA ASSEMBLE**




FIGURE 7.4 PADS OF PRODUCT FOR SOLDERING

REVISION:	ECR/ECN INFORMATION:	TITLE:			SHEET No.	
۸	EC No: <b>121094</b>	GNSS/WI	FI Combo Ceramic Ant	enna	<b>22</b> of <b>23</b>	
Α	DATE: 2017/08/25					
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	APPROV	ED BY:	
2030070001		Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong	2017/08/25	






FIGURE 7.5 RECOMMENDED FOOTPRINT ON PCB FOR SOLDERING

REVISION:	ECR/ECN INFORMATION:	TITLE:			SHEET No.
A	EC No: <b>121094</b>	GNSS/WIFI Combo Ceramic Antenna			<b>23</b> of <b>23</b>
	DATE: <b>2017/08/25</b>				
DOCUMENT NUMBER:		CREATED / REVISED BY:	CHECKED BY:	APPROVED BY:	
2030070001		Hai Liu 2017/08/25	Benson Liu 2017/08/25	Chris Zhong 2017/08/25	